Company Profile

Associated Construction Co. (K) Ltd.



ASSOCIATED CONSTRUCTION CO. (K) LTD

(CIVIL ENGINEERING CONTRACTORS) Elgon Road, Upper Hill, P. O. Box 31114-00600, Nairobi, Kenya Tel:254 -721-345416 / 254-733-271272 Email : nsb@associated.co.ke , acckl@associated.co.ke





TABLE OF CONTENTS

INTRODUCTION

COMPANY DETAILS

SCHEDULE OF MAJOR WORKS UNDERTAKEN

SCHEDULE OF PLANT AND EQUIPMENT

INTRODUCTION

Associated Construction Company (K) Ltd is a civil Engineering Construction Company offering a wide range of construction services tailored to add value to each project that the company is employed on.

The company combines local specialist contracting services with world class engineering firms in joint venture arrangement to produce a strong competitive advantage to both the company and for its clients.

The main areas of services are:

- a) Civil Engineering works in Roads, hard standing installations, river protection works.
- b) Bridge construction
- c) Marine works
- d) Geotechnical investigation
- e) Building and structural works.

Plant Resource Capacity

In Civil Engineering works Associated Construction Co. Ltd maintains its own plant and equipment capable of undertaking heavy earthworks, road works, and Asphalt production and laying.

In bridge construction work Associated Construction Co. (K) Ltd has developed a wide range of construction equipment for temporary works in the form of pontoons, trestles jacking frames capable of handling any magnitude of bridge works in both concrete and steel.

Associated Construction Co. (K) Ltd also has a 40 Ton capacity crane, and elaborate gantry systems for effective construction working over difficult terrains.

Associated Construction Co. (K) Ltd maintains joint venture arrangements with M/s Dorman Long Technology Ltd of the U.K for consulting and contracting services in bridge construction. A joint venture arrangement is also maintained with M/s Yerevan Steel Construction Co. Ltd. of the United Arab Emirates Dubai for heavy steel fabrication works.

In marine construction Associated Construction Co. (K) Ltd maintains piling equipment capable of undertaking all forms of piling works for offshore structures.

The capability of piling includes concrete piles; bottom drives steel piles bored piles. Associated Construction Co. (K) Ltd also maintains a joint venture arrangement with M/s Maru piling and geotechnical services for piling works and geotechnical investigations.

In building and structural works, Associated Construction Co. (K) Ltd has maintained plant and equipment to cover both concrete and steel structures.

COMPANY DETAILS

NAME OF COMPANY:

Associated Construction Co. (K) Ltd

DATE OF INCORPORATION:

 $18^{\rm th}$ June 1976 Registration No. C14635

US\$ 384,615.00

US\$ 384,615.00

Limited Liability Company Incorporated in the Republic of Kenya.

AUTHORISED CAPITAL

PAID UP CAPITAL

DIRECTORS:

Names	Nationality	Position
K.S. BANSAL	British	Chairman
N.S. BANSAL	Kenyan	Managing Director
REGISTRED OFFICE		Elgon Road, Upper Hill
		P. O. Box 31114 - 00600
		Tel : 0721 345416, 0733 271272
		Fax: 2715596
		Email: acckl@ associated .co.ke, nsb@associated.co.ke
		NAIROBI, KENYA
WORKSHOPS		Embakasi - Nairobi
BRANCH OFFICE		Kibos, Kisumu
REGISTRATION		
Ministry of Roads		Class A
Ministry of Public work	S	Class A
Ministry of Water Development		Class A
MEMBERSHIP		

Executive Member of the Roads and Civil Engineering Contractors Association (RACECA) Kenya. Kenya Association of Building and Civil Engineering Contractors (KABCEC). VSC Kenya

Certified Public Accountants (K)

Posta Sacco Plaza, 15th Floor

University Way

P. O. 46986 00100

Nairobi

PRINCIPAL BANKERS

Middle East Bank (K) Ltd

Milimani Road Branch

P.o. Box 47387 00100

<u>NAIROBI.</u>

Bank of Africa Ltd

Reinsurance Plaza, Taifa Road

P.O Box 69562 - 00400

<u>NAIROBI</u>

Kenya Commercial Bank

Kencom House

P. O. Box 48400 00100

NAIROBI

SCHEDULE OF MAJOR WORKS UNDERTAKEN

a) SCHEDULE OF ONGOING PROJECTS

I CERTIFY THAT THE WORKS INDICATRED HEREIN ARE BEING DONE BY US

.....

Signature

Date

SCHEDULE OF MAJOR WORKS UNDERTAKEN

b) SCHEDULE OF MAJOR ROAD AND BRIDGE WORKS COMPLETED

I CERTIFY THAT THE WORKS INDICATED HEREIN WERE DONE BY US

.....

Signature

Date



CONSTRUCTION TO BITUMEN STANDARD OF JUNCTION B3-NAIREGIE ENKARE ROAD (E445)



The contract comprised of construction to bitumen standard of 6km road with asphaltic concrete wearing course. The road base and sub base are in natural gravel material stabilized with cement. The works include drainage structures. Pipe culverts, box culverts and several bridges and box culverts.

Main contractor: ACCKL

Client: Narok County

Contract period **10 Months from September 2014**

Contract sum: US\$ 4.5 million

Contract status: Just Awarded

Value of completed to date: Nil

Physical Completion: **Nil**





REHABILITATION OF CONTROL BUILDING DAM/ INTAKE ACCESS ROAD FOR TURKWEL POWER STATION







The contract comprised of construction to bitumen standard of 7km road with asphaltic concrete wearing course. The road base and sub base are in natural gravel material stabilized with cement. The works include drainage structures. Pipe culverts, box culverts and several bridges and box culverts.

Main contractor: ACCKL

Client: Kenya Electricity Generating Co. Ltd

Contract period **12 Months**

Contract sum: US\$ 1.7 million

Contract status: Just Awarded

Value of completed to date: Nil

Physical Completion: Nil



RECONSTRUCTION OF THE ROAD LINKING GITHURAI 44 TO GITHURAI 45 AND CONSTRUCTION OF ACCESS TO THIKA GREENS







The contract comprised of construction to bitumen standard of 3km road with asphaltic concrete wearing course. The road base and sub base are in natural gravel material stabilized with cement. The works include drainage structures. Pipe culverts, box culverts and several bridges and box culverts.

Main contractor: ACCKL

Client: Nairobi Metropolitan

Contract period 18 Months from August 2013

Contract sum: US\$ 3.2 million

Contract status: **Ongoing**

Value of completed to date: US\$ 1.9 million

Physical Completion: **60%**



UPGRADING TO BITUMEN STANDARDS OF SIGALAGALA -MUSOLI -SABATIBUTERE ROADS (D260/E390)







The contract is comprised of upgrading to Bitumen standards of a 36 km road with asphalt concrete and single seal surface dressing on the carriage way with double seal surface dressing on the shoulders. The works also include improving the subgrade, lime improved subbase and cement improved base. The major work also includes construction of service roads, culverts, drainage and protection works.

Main contractor: ACCKL

Client: Kenya Rural Roads Authority

Contract period June 2012 to June 2015

Contract sum: US\$ 25 million

Contract status: **On going**

Value of completed to date: US\$ 4.6 million

Physical Completion: **30%**



CONSTRUCTION TO BITUMEN STANDARD OF BONDO SIAYA RANGALA ROAD



Earth works



Top soil stripping to spoil



Scaffolding and form work to bridge



The contract comprised of construction to bitumen standard of a 45km road with asphaltic concrete wearing course. The road base and sub base are in natural gravel material stabilized with cement. The works include drainage structures. Pipe culverts box culverts and several bridges and box culverts

Main contractor:	ACCKL	
Client:	Ministry o	f Roads
Contract period	October 20	008 to date
Contract sum:	US\$ 20 m	illion
Contract status:	Completed	1
Value completed to d	ate: US	\$.20m
Physical completion:	10	0%

Construction of box culvert

CONSTRUCTION TO BITUMENSTANDARD OF EBUYANGU EKERO ROAD C33





Base stabilization with cement



Earthworks



Base priming



Surface Dressing

The contract comprised of construction to bitumen standard of a 30km road with 18km double surface dressing and 12km in asphaltic concrete. The road base and sub base are in natural gravel material stabilized with cement. The works include drainage structures. Pipe culverts box culverts and widening of 45m long bridge across Yala River.

The works are substantially complete and 85% of the road has already been opened to the traffic.

Main contractor:	ACCKL
Client:	Ministry of Roads and Public works
Contract period:	June 2007 to date
Contract sum:	US\$16 million
Contract status:	Completed
Value completed to d	late: US\$16m
Physical completion:	100%



EMERGENCY MAINTENANCE OF KISUMU-KAKAMEGA (A1) ROAD







The contract comprised of emergency maintenance of a 50km road with asphaltic concrete wearing course. The works include reinstatement or repairs of shoulders to pavement, reconstructions in sections, patching, regulations and finally overlay. The works also include culverts and drainage works.

Main contractor: ACCKL

Client: Kenya National Highways Authority

Contract period June 2010 to May 2011

Contract sum: US\$ 4 million

Contract status: Completed

Value of completed to date: US\$ 4 million

Physical Completion: **100%**



CONSTRUCTION OF NDAU SEAWALL - LAMU DISTRICT







The contract is comprised of constructing a new sea wall 1300m long along Ndau, construction of a new seawall 300m at Kizingitini including repair of existing sea wall and breakwater. Repair about 250m on Lamu seawall at Lamu. All the construction includes concrete paved walkway, staircases, mooring bollards and boat slipways along the seawall.

Main contractor: ACCKL

Client: Ministry of Public Works

Contract period June 2012 to June 2015

Contract sum: US\$ 3.5 million

Contract status:

On going

Value of completed to date: US\$ 1.6 million

Physical Completion: 60%





Completed section of seawall



Seawall stair case



Break water core



Seawall

Construction of 1400 m of seawall in Faza Island along the sea shore by excavating in water logged loose sand and backfilling in gunny bags and coral boulders to base of foundation over which a concrete foundation 1.5m x 0.5m mass concrete was coast. The sea wall is constructed in class A1 concrete blocks with a 300mm grouted coral boulder behind the wall.

A filter fabric is provided behind the wall and clean sea sand is backfilled behind the wall. The top of the wall is provided with a pedestrian pavement and drainage provisions

Ndau break water

This is a400m long break water built into the sea in coral boulder core 5m high over which a filter fabric is placed and large break water boulders placed over it. The lee ward side is lined with grouted boulders with a provision of stairs and bollards for marine vessel use

Main contractor:	ACCKL
Client:	Ministry of Public works
Contract period:	October 2007 to October 2009
Contract sum:	US\$5 million
Contract status:	Completed
Value completed to c	late: US\$.5 m
Physical completion:	100%



WAIYAKIWAY-REDHILL ROAD IN NAIROBI CITY COUNCIL







The contract is comprised of constructing a new road approximately 5km to gravel standards. The road sub base and base are in natural material. Works also include culverts and drainage works.

Main contractor: ACCKL

Client: Kenya Urban Roads Authority

Contract period Feb 2011 to May 2012

Contract sum: US\$ 2.5 million

Contract status: Completed

Value of completed to date: US\$ 2.5 million

Physical Completion: **100%**



CONSTRUCTION RUNDA ESTATE WHISPERS ESTATE LINK BRIDGE



The 3 cell 5m x 2m box culvert



The approach Road

Construction of a 3 cell box culvert 5m x 2m and 800 meters of approach road on an embankment fill in soft and hard material. The section around the box culvert location was swampy ground that required substantial boulder bottoming to improve on the bearing capacity. The pavement structure is hand packed stone sub base and base and asphaltic concrete wearing course.

Drainage structures comprise of pipe culverts Invert block drains and slotted drains.

Main contractor:	ACCKL
Client:	Ministry of Roads
Contract period:	June 2007 to June 2008
Contract sum:	US\$ 2million
Contract status:	Completed 2008



Drainage works and embankment

CONSTRUCTION OF MASALANI SUSPENSION BRIDGE





Concrete construction to pier base and stem



Temporary trestles to deck construction



Stiffening girder installation



Cross beam and troughing installation

This is a 136m long self anchored steel suspension bridge built across river Tana. The foundation is in concrete bored piles 600mm diameter 25m below pile cap. The support structures of abutments and pier are in reinforced concrete.

The stiffener girders, bracings and towers are in steel and the main cables comprise of 7 no. 45mm diameter fully locked coil ropes.

The deck is in steel troughing 9mm thick with 300mm concrete topping.

Fabrication drawings for the Bridge steel was done by associated and fabrication done in Dubai. Cables design were done by Associated and manufactured in UK and Germany. Erection done by Associated Construction Co. Ltd using local resources.

Main contractor	: ACCKL
Client:	Ministry of Roads and Public works
Contract period	: June 2004 to July 2007
Contract sum:	US\$ 8.6 million
Contract status:	Completed 2007

CONSTRUCTION OF MASALANI SUSPENSION BRIDGE





Tower installation



Cable installation



The completed bridge deck

Major construction high lights

The foundations were originally in steel H sections but we offered an alternative and designed for 600mm concrete bored piles.

The construction mode for the bridge required that the deck be erected first before installation of cable and transfer of loading from temporary supports to cable system. An elaborate temporary support was designed, fabricated and installed by piling into the river to provide for this support. The system included a jacking frame for camber provision and load transfer

The steel for the deck beams and towers were to be sourced partly from an old bridge and partly new parts. The old parts were unserviceable and a complete use of new parts was required. There being no design for the bridge we undertook to do the design, prepare fabrication drawing and fabricated the steel components

The construction design and the erection of the bridge deck, cables and hanger bars was done entirely by local staff and resources.

All temporary work were locally fabricated and installed on the site by the main contractor.



REHABILITATION OF MOKOWE AND MANDA JETTIES LAMU



Driving concrete sheet piles



Rehabilitated jetty with fenders



Pontoon



Breaking of jetty for reconstruction

Rehabilitation of a dilapidated marine jetty by reconstruction of damaged deck and staircase concrete due to steel rust, replacement of worn out fenders. Application of protective epoxy treatment to concrete surfaces.

Construction of new steel pontoons and approach steel ladders

Protection works by way of piling concrete sheet piles to a damaged section of sea wall.

Construction of sea wall 200meter long with foundation in coral boulders over which a concrete foundation 1.5m x 0.5m mass concrete. The sea wall is constructed in class A1 concrete blocks with a 300mm grouted coral boulder behind the wall. and filter fabric behind the wall and clean sea sand is backfilled behind the wall. The top of the wall is provided with a pedestrian pavement and drainage provisions

Main contractor:	ACCKL
Client:	Ministry of Public works
Contract period:	July 2006 to January 2008
Contract sum:	US\$3 million
Contract status:	Complete 2008



KENYA SHELL: RAILWAY SIDING UPGRADE AT MOMBASA TERMINAL



Turnout track laid on base concrete



Plain track cast in topping concrete



Turnout track cast in topping concrete

Construction of a 300 meter long Rail Track siding with a 60 meter loop line all in a reinforced concrete base to the LPG siding for Kenya Shell/Bp Ltd in Shimanzi Mombasa. The works comprised of removal of existing rail siding, excavating ground to level and concreting a slab on grade with the rails in place.

The track included plain track. At grade crossing track and a turnout all provided in concrete base.

The works also comprised provision ducts for crossing of services and drainage structures.

Main contractor:	ACCKL
Client:	Kenya Shell BP Ltd
Contract period:	January 2007 to December 2007
Contract sum:	US\$ 0.95 million
Contract status:	Complete 2006





Driving Concrete sheet piles



Completed seawall section concrete blocks



Completed sea wall section armour blocks

Construction of 200 m of seawall in Faza island along the sea shore by excavating in water logged loose sand and backfilling in gunny bags and coral boulders to base of foundation over which a concrete foundation 1.5m x 0.5m mass concrete was coast. The sea wall is constructed in class A1 concrete blocks with a 300mm grouted coral boulder behind the wall.

A filter fabric is provided behind the wall and clean sea sand is backfilled behind the wall. The top of the wall is provided with a pedestrian pavement and drainage provisions

Protection works to existing seawall by driving 3.5m long precast concrete sheet piles over an 80 m section

Main contractor:	ACCKL
Client:	Ministry of Public works
Contract period:	October 2004 to December 2005
Contract sum:	US\$1.5 million
Contract status:	Complete 2006



IMPROVEMENTS TO RAILWAY SIDINGS AT TOTAL DEPOT MOMBASA



Rafted Track turnout laid in concrete



Track in concrete



Steel reinforcement to base concrete

The works involved the removal of the old railway siding at the terminal in Mombasa construction of a temporary diversion, remedying of a difficult soggy foundation, provision of a reinforced concrete raft on a compacted hardcore base, laying of the rail track and all accessories the length of track was 300m long. Provision of rail track turn out and drainage and hard standing.

Main contractor:	ACCKL
Client:	Total Kenya Ltd.
Contract period:	February 2000 to July 2000
Contract sum:	US\$ 0.15 million
Contract status:	Complete 2003









The works involved the rehabilitation and reconstruction to gravel standard rural roads and bridges in Bungoma district western Kenya. The scope of the works included gabion protection works, reconstruction of bridge embankments and protection of abutments, aprons and approaches, earthworks reconstruction of road verges, provision of gravel base and wearing course and drainage system.

The roads covered were D279, C42, D277, and D283 all totalling 59 km

Main contractor:	ACCKL
Client:	Office of President El nino emergency project.
Contract period:	July 2000 to April 2001
Contract sum:	US\$ 3.15 million
Contract status:	Complete 2001









The works involved the rehabilitation and reconstruction to gravel standard rural roads and bridges in Bungoma district western Kenya. The scope of the works included gabion protection works, reconstruction of bridge embankments and protection of abutments, aprons and approaches, earthworks reconstruction of road verges, provision of gravel base and wearing course and drainage system.

The roads covered were C32, D281, D275, D278, D270, E1239, E1237, E308, and E309 all totalling 67Km

Main contractor:	ACCKL
Client:	Office of President El nino emergency project.
Contract period:	July 2000 to April 2001
Contract sum:	US\$ 2.65 million
Contract status:	Complete 2001

CONSTRUCTION AND REHABILITATION OF TOWN ROADS IN BUNGOMA, BUSIA AND KAKAMEGA. KENYA URBAN TRANSPORT INFRASTRUCTURE PROJECT(KUTIP): PACKAGE 14









The works comprised of the upgrading of existing earth gravel roads to bituminous standard involving extensive earthworks, provision of natural gravel sub base stabilized gravel base and asphaltic concrete wearing course. The works also included rehabilitation of existing worn out bituminous road surfaces with premix and surface dressing, provision of drainage systems, bus bays, cycle tracks and road furniture.

The total length of roads were

Kakamega:	12 roa	ds 11 km
Bungoma:	10 roa	ds 5 km
Busia:	3 road	s 4.4 km
Main contractor:		ACCKL
Client:		Ministry of Local Government
Contract perio	od:	December 1998 to March 2000
Contract sum:		US\$ 8.59 million
Contract statu	s:	Complete 1998

CONSTRUCTION AND REHABILITATION OF TOWN ROADS IN HOMA BAY AND KISII ROADS: KENYA URBAN TRANSPORT INFRASTRUCTURE PROJECT(KUTIP): PACKAGE 15









The works comprised of the upgrading of existing earth gravel roads to bituminous standard involving extensive earthworks in expansive clays and red coffee soils, provision of natural gravel sub base stabilized gravel base and asphaltic concrete wearing course. The works also included rehabilitation of existing worn out bituminous road surfaces with premix and surface dressing, provision of drainage systems, bus bays, cycle tracks and road furniture.

The total length of roads were

Kisii: 10 roads 8.5 km

Homa Bay: 5 roads 4.5 km

Main contractor:	ACCKL
Client:	Ministry of Local Government
Contract period:	December 1998 to March 2000
Contract sum:	US\$ 6.05 million
Contract status:	Complete 1999



EMMERGENCY REPAIR WORKS KIBWEZI SECTION THANGE BRIDGE



Twin cell 1200mm pipe culvert



Reinforcement to top slab box culvert



The completed 2 cell 4.5m x 4.5m BC



The works were as result of flood damage to the road causing an insufficient pipe culvert to be overloaded with storm flow leading to damage of the road section.

The works comprised of construction of a diversion and the construction of a twin cell 4.5m x 4.5m box culvert complete with wing walls and backfilling to formation level, gabion protection works construction and maintenance of the road section to bitumen finish.

Main Contractor: ACCKL

Client:

Ministry of Roads and Public works.

Contract period: June 1998 to October 1998

Contract sum: US\$ 2.5 million

Contract status: Complete 1998

Cement stabilizing of approach road



CONSTRUCTION OF ADAMSON FALLS BRIDGE AND APPROACH ROADS



Head treatment to bored piles



Concrete construction pier



The Bailey bridge



The Bailey bridge

The works comprised of the construction of 90 meter steel Bailey bridge on reinforced concrete abutments and piers in Meru National park across the Tana River.

The foundation were concrete pad foundations on rock except for one pier whose foundation was on 600mm diameter concrete bored piles

There were road approaches 5 km long and extensive river and bridge protection works

Main Contractor:	ACCKL
Client:	Kenya Wild Life Services
Consultant:	Churchi Githinji and associates
Contract period:	January 1998 to November 1998
Contract sum:	US\$ 2.5 million
Contract status:	Complete 1998

BARICHO BRIDGE AND APPROACH ROADS





Concrete bored piles



Concrete construction to pier



Complete Piers South end

Construction of 6 kilometres of approach roads to gravel standard in earth fill 30,000m3. The works comprised of the excavations and construction of bridge pile and pad foundations, pile head treatment and construction of a reinforced concrete abutments and piers and related river training works.

The main bridge foundations were on 600mm diameter concrete bored piles

Main contractor:	ACCKL
Client:	Ministry of Roads and Public works
Contract period:	December 1990 to December 1992
Contract sum:	US\$ 1.9 million
Contract status:	Complete 1995

CONSTRUCTION OF NGAI NDEITHYA BRIDGE







Bridge Construction under rail traffic



The completed structure

Following heavy rains floods damaged an approach embankment to an arch culvert for a railway line. This resulted in an accident of a passenger killing several people.

A temporary bridge was constructed over the damaged area to facilitate flow of rail traffic and construction of a permanent bridge.

A bridge was constructed to increase the opening of the river which was originally an arch culvert. The works comprised of excavation in soft and hard material, provision of false work to protect existing temporary rail track provisions and construction of a reinforced concrete bridge on pier and abutment.

Upstream of the bridge extensive earthworks to river training works was carried out including diversions and cofferdams.

Main Contractor:	ACCKL
Client:	Kenya Railways Corporation
Contract period:	October 1993 to May 1994
Contract sum:	US\$ 1.4 million
Contract status:	Complete 1994



CONSTRUCTION OF FOOT BRIDGES ON THIKA ROAD AND WESTLANDS



Working under traffic



Hoisting of precast girders



The completed structure

Due to heavy pedestrian traffic over very busy and fast roads foot bridges were to be constructed across dual carriage roads on Thika road and Waiyaki way in Nairobi.

Two bridges were constructed of 22m length.

The construction comprised of reinforced concrete piers and abutments and precast concrete deck beams with an in-situ concrete deck. The beams were cast on the ground and lifted by cranes into position. The deck was formed from permanent formworks and cast to tie into the beams.

Main Contractor:	ACCKL
Client:	Ministry of Roads and Public Works
Contract period:	June 1997 to June 1998
Contract sum:	US\$ 0.85million
Contract status:	Complete 1997





The bridge with protection on left



Bank protection in gabions



Bank protection and groynes

Bura Bridge is a steel cable stay bridge constructed across the Tana River on a position where the upstream side of river curves sharply into the bridge. This created dangers to erosions on the banks compromising the abutment fill and support.

The protection works comprised the construction of groynes in the Tana River to protect the river embankments and gabions on the eastern side of the river approaching the Bura Bridge.

This was done using rock fill, gabions and boulders totalling approximately 100,000 m^3 .

Main contractor:	ACCKL
Client:	Ministry of Roads and Public Works
Contract period:	January 1995 to December 1996
Contract sum:	US\$ 3.5million
Contract status:	Complete 1990

ASSOCIATED CONSTRUCTION CO (K) LTD. P.O BOX 31114-00600, NAIROBI-KENYA: VEHICLES AND EQUIPMENT LIST:

All plant and equipment in this list are owned by Associated construction co. Ltd

NO	VEHICLE/MACHINE	QTY NO	TYPE/MODEL		/REG lo.
1	MOTOR GRADER	1	MOTOR GRADER CAT 140H		
2		2	MOTOR GRADER CAT 140H		
3		3	MOTOR GRADER CAT 140H	KAX	9955
4		4	MOTOR GRADER CAT 120H	КАН	228Q
5		5	MOTOR GRADER CAT 120H	KAL	746F
6		6	MOTOR GRADER SANY	КАУ	448F
7		7	MOTOR GRADER SANY	КАУ	449F
8		8	MOTOR GRADER KOMATSU GD623A	KBE	176V
9		9	MOTOR GRADER KOMATSU GD623A	KBE	762V
10	DOZERS	1	DOZER CAT D8R	KBE	442M
11		2	DOZER KOMATSU D85A-21	KAZ	015L
12		3	DOZER KOMATSU D85A-18	KAZ	944A
13	EXCAVATORS	1	CAT 312B		
14		2	EXCAVATOR CAT 330B	КАУ	830A
15		3	EXCAVATOR KOMATSU PC 200-3	KZQ	049
16		4	EXCAVATOR KOMATSU PC 200-6	KAZ	279V
17		5	EXCAVATOR VOLVO EC 210B LC	KBE	629V
18		6	EXCAVATOR VOLVO EC 290B LC	KBE	640V
19		7	EXCAVATOR VOLVO EC 210B LC	KBG	253M
20	DRUM ROLLERS	1	DRUM ROLLER HAMM 2420		
21		2	DRUM ROLLER BOMAG		
22		3	ROAD MARSHALL		
24		5	DRUM ROLLER DYNAPAC CC 222CF	KBJ	156E
25		6	DRUM ROLLER DYNAPAC CA 300D	KBF	030M
26		7	DRUM ROLLER DYNAPAC CA 300D	KBG	660V
27		8	DRUM ROLLER DYNAPAC HAMM 2420	KAL	164K
28		9	DRUM ROLLER HAMM 3412	KAX	236P
29		10	DRUM ROLLER HAMM 3412	KAZ	106V
30		11	DRUM ROLLER HAMM 3412	KBG	415K
31		12	DRUM ROLLER HAMM 3412	КВН	497C
32		13	DRUM ROLLER INGERSALLAND	KAG	159G
33	WHEEL LOADERS	1	WHEEL LOADER CAT 920	KAB	810K
34		2	WHEEL LOADER HYUNDAI HL 770-7A	KBB	264F
35	TRACK SHOVELS	1	TRACK SHAVEL CAT 953	KAC	157Q
36		2	TRACK SHAVEL KOMATSU D66S	KAW	254V

NO	VEHICLE/MACHINE	QTY NO	TYPE/MODEL		/REG lo.
37	HEAVY TRUCK TIPPERS	1	BENZ TRUCK	KAB	644P
38		2	BENZ TRUCK HIAB	KAB	645P
39		3	25 TON FUSO TIPPER TRUCK	KAE	516U
40		4	30 TON FUSO TIPPER TRUCK	KAG	673V
41		5	FUSO TRUCK HORSE	KAG	674V
42		6	30 TON FUSO TIPPER TRUCK	KAG	855R
43		7	25 TON FUSO TIPPER TRUCK	КАН	844Q
44		8	25 TON BENZ TIPPER TRUCK	KAJ	197 <i>G</i>
45		9	25 TON BENZ TIPPER TRUCK	KAJ	761J
46		10	15 TON TATA TIPPER TRUCK	KAL	843 <i>G</i>
47		11	15 TON TATA TIPPER TRUCK	KAL	001 <i>G</i>
48		12	20 TON FUSO TIPPER TRUCK	KAL	895T
49		13	20 TON FUSO TRUCK L/CHASSIS	KAM	427M
50		14	30 TON FUSO TIPPER TRUCK	KAQ	404Q
51		15	30 TON FUSO TIPPER TRUCK	KAR	007P
52		16	30 TON FUSO TIPPER TRUCK	ΚΑΤ	677L
53		17	30 TON FUSO TIPPER TRUCK	KAV	344M
54		18	FUSO LOW-LOADER HORSE	KAV	377M
55		19	25 TON BENZ TIPPER TRUCK	KAW	037P
56		20	30 TON FAW TIPPER TRUCK	KAX	277G
57		21	30 TON FAW TIPPER TRUCK	KAX	377G
58		22	30 TON FAW TIPPER TRUCK	ΚΑΧ	968D
59		23	30 TON FAW TIPPER TRUCK	KAX	971D
60		24	20 TON FAW TIPPER TRUCK	KAZ	450T
61		25	20 TON FAW TIPPER TRUCK	KAZ	451T
62		26	FUSO WATER TANKER	KAJ	366E
63		27	25 TON BENZ TIPPER TRUCK	KBA	240K
64		28	25 TON BENZ TIPPER TRUCK	KBA	590V
65		29	25 TON BENZ TIPPER TRUCK	KBB	241K
66		30	20 TON FAW TIPPER TRUCK	КВС	325V
67		31	20 TON FAW TIPPER TRUCK	КВС	890Z
68		32	20 TON FAW TIPPER TRUCK	КВС	893Z
69		33	20 TON FAW TIPPER TRUCK	KBD	436D
70	LIGHT TRUCKS	1	3 TON FAW TRUCK	KBA	016K
71		2	MITSUBISHI 3 TON TRUCK	KBD	092Q
72		3	MITSUBISHI 3 TON TRUCK	KBG	153F
73		4	MITSUBISHI FH CANTER	KAX	6675

NO	VEHICLE/MACHINE	QTY NO	TYPE/MODEL	REF/REG No.
			MITSUBISHI 10,000 LITRES DIESEL	
74	DIESEL TANKERS	1	TANKER	KBG 586K
			MITSUBISHI 10,000 LTRES DIESEL	
75		2	TANKER	KBB 590T
76	VEHICLES P/UPS	1	TOYOTA L/CRUISER 1 TON P/UP 4X4	KAA 242F
77		2	TOYOTA L/CRUISER 1 TON P/UP 4X4	KAD 693X
78		3	TOYOTA HILUX DOUBLE CAP P/UP 4X4	KAN 542R
79		4	TOYOTA HILUX DOUBLE CAP P/UP 4X4	KAN 543R
80		5	TOYOTA HILUX DOUBLE CAP P/UP 4X4	KAW 559V
81		6	TOYOTA HILUX DOUBLE CAP P/UP 4X4	KAW 560V
82		7	TOYOTA HILUX SINGLE CAP 4X4	KAY 106X
83		8	TOYOTA HILUX DOUBLE CAP P/UP 4X4	KAY 141A
84		9	TOYOTA HILUX DOUBLE CAP P/UP 4X4	KAY 142A
85		10	TOYOTA HILUX DOUBLE CAP P/UP 4X4	KAY 361X
			MITSUBISHI L200 1 TON SINGLE CAP	
86		11	P/UP 2X4	KAY 708F
			MITSUBISHI L200 1 TON SINGLE CAP	
87		12	P/UP 2X4	KAY 719F
			MITSUBISHI L200 1 TON SINGLE CAP	
88		13	P/UP 2X4	KAZ 283G
			MITSUBISHI L200 1 TON SINGLE CAP	
89		14	P/UP 2X4	KAZ 315G
		45	MITSUBISHI L200 DOUBLE CAP P/UP	
90		15		KBA 046N
91		16	MISTUBISHI L200 1 TON SINGLE CAP P/UP 4X4	KBB 808 <i>G</i>
91		10	TOYOTA HILUX DOUBLE CAP P/UP 4X4	KBD 823P
92		17	TOYOTA HILUX DOUBLE CAP P/UP 4X4	KBD 823P
93		10	MITSUBISHI L200 DOUBLE CAP P/UP	NDU 024P
94		19	4X4	KBD 892W
		17	MITSUBISHI L200 DOUBLE CAP P/UP	
95		20	4X4	KBD 894W
			MITSUBISHI L200 DOUBLE CAP P/UP	
96		21	4X4	KBD 895W
			MITSUBISHI L200 DOUBLE CAP P/UP	
97		22	4X4	KBD 893W
			MITSUBISHI L200 1 TON SINGLE CAP	
98		23	P/UP 4X4	KBG 203K
			MITSUBISHI L200 1 TON SINGLE CAP	
99		24	P/UP 4X4	KBG 204K
100		25	TOYOTA HILUX 1 TON P/UP 4X4 WD	KWF 950

NO	VEHICLE/MACHINE	QTY NO	TYPE/MODEL	REF/R	EG No.
101	VEHICLES SALOON	1	MITSUBISHI SALOON	KAG	193A
102		2	TOYOTA L/CRUISER VX HDJ80	KAJ	290V
103		3	TOYOTA L/CRUISER VX HDJ81	KAK	026C
104		4	ΤΟΥΟΤΑ PRADO	KAP	755C
105		5	PEUGEOT SALOON	KAQ	390 <i>G</i>
106		6	TOYOTA L/CRUISER VX	KAS	298Y
107		7	NISSAN URVAN	KAV	196Z
108		8	TOYOTA L/CRUISER VX	KAV	290T
109		9	TOYOTA SALOON	KAW	188 <i>A</i>
110		10	ΤΟΥΟΤΑ PRADO	KAX	258Y
111		11	MITSUBISHI LANCER	КАУ	146U
112		12	TOYOTA DUET SALOON	КАУ	421Z
113		13	MITSUBISHI PAJERO	KAZ	771G
114		14	FORD EVEREST SALOON	KBB	250 <i>G</i>
115		15	VOLVO SALOON	KBD	490F
116		16	TOYOTA FORTUNER	КВН	985M
117	MOTOR BIKES	1	SAHARA MOTOR BITE	KAL	780V
118		2	MOTOR BIKE	КАУ	868K
119	MISC PLANTS	1	SAKAI SOIL MIXER	KAZ	938A
120		3	FARM TRACTOR SOLANIKA	KBD	282W
121		5	CLAAS TRACTOR & SOIL STABILIZER	KAZ	297B
122		6	CLAAS TRACTOR & SOIL STABILIZER	KBH	519C
123		7	FORKLIFT - 5 tons	КJТ	344
124	AIR COMPRESSORS	1	DIESEL DEUTZ ENGINE		
125		2	DIESEL DEUTZ ENGINE		
126		3	ELECTRIC 100 LITRES		
127		4	DIESEL CUMMINS C50		
128		5	DIESEL LISTER ENGINE		
129		6	PETROL HONDA ENGINE		
130		7	PETROL HONDA ENGINE		
131		8	PETROL HONDA ENGINE		
132		9	PETROL CHINESE ENGINE		
133	BIG CONCRETE MIXERS	1	WINGET 400R		
134		2	WINGET 500R NO. 1		
135		3	WINGET 500R NO. 2		
136		4	CHINESE NO. 1		
137		5	CHINESE NO. 2		
138		6	CHINESE NO. 3		

NO	VEHICLE/MACHINE	QTY NO	TYPE/MODEL	REF/REG No.
139	SMALL CONCRETE MIXERS	1	DIESEL ENGINE	NO 1
140		2	DIESEL ENGINE	NO.2
141		3	DIESEL ENGINE	NO.3
142		4	DIESEL ENGINE	NO 4
143		5	DIESEL ENGINE	NO 5
144		6	DIESEL ENGINE	G
145		7	DIESEL ENGINE	F
146	MOBILE CONCRETE MIXER	1	CAR MIX	
147	DUMPERS	1	CHINESE NO. 1	
148		2	CHINESE NO. 2	
149	PEDESTRIAN ROLLERS	1	DYNAPAC 650HP NO.1	
150		2	DYNAPAC 650HP NO. 2	
151		3	DYNAPAC 750HP	
152	GENERATORS	1	AIRMARSHALL	NO.1
153		2	DIESEL DEUTZ ENGINE	NO.2
154		3	DIESEL DEUTZ ENGINE	NO.3
155		4	DIESEL NISSAN ENGINE	NO.4
156		5	PETROL HONDA ENGINE	NO.5
157		6	PETROL HONDA ENGINE	NO.6
158		7	PETROL HONDA ENGINE	NO.7
159		8	PRAMAC 30 KVA DEUTZ ENGINE	NO.8
160	PRESSURE WASHERS	1	CHINESE	NO.1
161		2	CHINESE	NO.2
162		3	ITALIAN	NO.3
163		4	ITALIAN	NO.4
164	WATER PUMPS 2"	1	PETROL HONDA ENGINE	
165	WATER PUMPS 3"	1	PETROL HONDA ENGINE	
166		2	PETROL HONDA ENGINE	
167		3	PETROL HONDA ENGINE	
168	WATER PUMPS 4"	1	DIESEL ENGINE	
169		2	DIESEL ENGINE	
170		3	DIESEL ENGINE	
171		4	DIESEL ENGINE	
172		5	DIESEL ENGINE	
173	WATER PUMPS 6"	1	DIESEL ENGINE	
174	WATER BOWZERS	1	LOCALLY MADE	NO. 1
175		2	LOCALLY MADE	NO.2
176	FARM TRAILER	1	LOCALLY MADE	
177	BLOCK MAKING MACHINE	1	LOCALLY MADE	

NO	VEHICLE/MACHINE	QTY NO	TYPE/MODEL	REF/REG N₀.	
178	VIBRATOR MACHINES	1	PETROL HONDA ENGINE	NO. 1	
179		2	PETROL HONDA ENGINE	NO. 2	
180		3	PETROL HONDA ENGINE	NO. 3	
181		4	PETROL HONDA ENGINE	NO. 4	
182		5	PETROL HONDA ENGINE	NO. 5	
183		6	PETROL HONDA ENGINE	NO. 6	
184		7	PETROL HONDA ENGINE	N	D. 7
185	PLATE COMPACTOR	1	PETROL HONDA ENGINE		
186	MOTOR BOAT ENGINE	1	УАМАНА 40 НР		
187	MOTOR BOAT	1	2 X 140 HP YAMAHA ENGINES		
188	ASPHALT EQUIPMENT	1	ASPHALT PLANT SPEED CRAFTS		
189		2	PAVER DYNAPAC		
190		3	BITUMEN DISTRIBUTOR	KBD	743P
191		4	CHIPS SPREADER	KBB	342A
192		5	DYNAPAC P.T.R ROLLER		
193	LOW-LOADERS	1	HIGH BED 40 TONS CAPACITY		
194		2	LOW BED 120 TONS CPAPCITY		
195	CRANES	1	ROUGH TERRAIN COLES CRANE 40 TON		
196		2	CRAWLER CRANE 20 TON		
	MARINE PILING		40 TON FLOATING PONTOON WITH		
197	EQUIPMENT	1	JACKING TRESTLE		
			15 TON PONTOON MOUNTED WITH		
198		2	PILING EQUIPMENT		
			25 TON BARGE MOUNTED WITH PILING		
199		3	UNIT		

The total value of the plant and equipment the Company owns exceeds US\$ 10,000,000/00

ASPHALT PLANT AND EQUIPMENT



Asphalt Plant





Bitumen sprayer



Chip spreader



Asphalt works

Bitumen sprayer



Paver

TIPPERS













GRADERS AND STABILISERS













EXCAVATORS AND DOZERS





















ROLLERS













WHEEL LOADERS









TRACTORS AND MIXERS





MISCELLENEOUS MARINE AND BRIDGE EQUIPMENT



40 Ton rough terrain crane



20 ton pontoon with piling equipment



Hi Hub lorry



40 ton pontoon barge with lifting trestle



Piling barge in sea



crawler crane with diesel piling hammer



Dumpers



Low loader

